

RIVERBEND PRODUCE LIMITED

Coolstore 3 — Glycol Chilling Upgrade

Brief prepared from the client specification.

Scope

Replacement of the existing direct-expansion plant serving Coolstore 3 with a glycol system, comprising a two-compressor pack, evaporative condenser, plate heat exchanger, glycol circulation and four new unit coolers within the store.

The existing plant is to remain in service until the new system is commissioned.

One changeover weekend is available, 14–15 November 2026.

Design criteria

||| |---|---| | Store volume | **4,200 m³** | | Design room temperature | **0 °C to +2 °C** | | Calculated operational room load | **480 kWR including margin for future expansion** | | Product | **pipfruit, palletised, 18 °C at intake** | | Pulldown | **full room from 18 °C to 2 °C within 36 hours** | | Glycol | **mono-propylene, 35%** | | Ambient design | **30 °C db / 21 °C wb** |

What the client asked for

- Compressors shall be fitted with variable speed drives.
 - Glycol circulation shall be duty/standby with a dedicated defrost circuit.
 - The new plant shall be supplied from a new distribution board in the plant room, fed from the existing main switchboard.
 - All motors shall be supplied with starters or drives as appropriate to the equipment.
 - Controls shall integrate with Riverbend's existing Ignition SCADA.
 - As-built drawings, operating and maintenance manuals, and operator training are to be included.
 - Producer statements are required for pipework supports and for the pressure system.
 - Tenderers shall provide prices against each of the following.
-

Engineer must decide

The specification leaves these open.

- **engineer to confirm** — The tenderer is to confirm available spare capacity

- **left to the engineer** — as appropriate to the equipment
- **to be provided** — is to be provided with the tender
- **selection decision** — capable of 50% of duty, arranged for duty/standby operation with automatic changeover

Required with the tender

- A schedule of connected load, starter type and control points is to be provided with the tender.
- Tenderers shall provide prices against each of the following.
- Tenders close 3 October 2026.

Schedule of prices

Ref	Description	--- ---	7.1	Compressor pack, including drives	7.2	Evaporative condenser
7.3	Chiller plate heat exchanger	7.4	Glycol circulation — pumps, tanks and controls	7.5	Unit coolers	7.6
7.6	Glycol pipework, valves and insulation	7.7	Installation labour, supervision and consumables	7.8	Electrical power, control wiring and SCADA	7.9
7.9	As-built documentation, training, O&M	7.10	Commissioning, glycol charge and spares	7.11	Twelve months defects liability and routine maintenance	

Bron: Riverbend-Q900142-Brief.md