

RIVERBEND PRODUCE LIMITED

Coolstore 3 — Glycol Chilling Upgrade

Request for Proposal · RBP-2026-014 · Issued 4 September 2026

Riverbend Produce Limited invites proposals for the design, supply, installation and commissioning of a glycol chilling upgrade to Coolstore 3 at 214 Kereru Road, Hastings.

1.0 Scope of works

Replacement of the existing direct-expansion plant serving Coolstore 3 with a glycol system, comprising a two-compressor pack, evaporative condenser, plate heat exchanger, glycol circulation and four new unit coolers within the store.

The existing plant is to remain in service until the new system is commissioned. One changeover weekend is available, 14–15 November 2026.

2.0 Design criteria

|| | | --- | --- | | Store volume | 4,200 m³ | | Design room temperature | 0 °C to +2 °C | | Calculated operational room load | 480 kWR including margin for future expansion | | Product | pipfruit, palletised, 18 °C at intake | | Pulldown | full room from 18 °C to 2 °C within 36 hours | | Glycol | mono-propylene, 35% | | Ambient design | 30 °C db / 21 °C wb |

3.0 Equipment

Two compressors are required, each capable of 50% of duty, arranged for duty/standby operation with automatic changeover. Compressors shall be fitted with variable speed drives.

Four unit coolers are to be installed within Coolstore 3, each nominally 55 kWR on glycol, with EC fans and hot-gas defrost.

Glycol circulation shall be duty/standby with a dedicated defrost circuit.

Refrigeration drawings: the proposed arrangement is shown on drawing Q900142 Rev A.

4.0 Electrical

The new plant shall be supplied from a new distribution board in the plant room, fed from the existing main switchboard. The tenderer is to confirm available spare capacity.

All motors shall be supplied with starters or drives as appropriate to the equipment. A schedule of connected load, starter type and control points is to be provided with the tender.

Controls shall integrate with Riverbend's existing Ignition SCADA.

5.0 Documentation and training

As-built drawings, operating and maintenance manuals, and operator training are to be included. Producer statements are required for pipework supports and for the pressure system.

6.0 Commissioning

Full commissioning including pulldown demonstration, defrost cycle proving, and a 12-month defects liability period with routine maintenance.

7.0 Schedule of prices

Tenderers shall provide prices against each of the following.

Ref Description --- ---	7.1 Compressor pack, including drives	7.2 Evaporative condenser
7.3 Chiller plate heat exchanger	7.4 Glycol circulation — pumps, tanks and controls	7.5 Unit coolers
7.6 Glycol pipework, valves and insulation	7.7 Installation labour, supervision and consumables	7.8 Electrical power, control wiring and SCADA
7.9 As-built documentation, training, O&M	7.10 Commissioning, glycol charge and spares	7.11 Twelve months defects liability and routine maintenance

Prices shall be exclusive of GST. Tenders close 3 October 2026.

This is a fictional specification prepared for demonstration purposes.